




BARGHAUSEN

TECHNICAL INFORMATION REPORT

Brown Bear - New Build

55 N.W. Gilman Boulevard
Issaquah, Washington

City/County File No. TBD



Prepared for:
Car Wash Enterprises, Inc
3977 Leary Way N.W.
Seattle, WA

April 3, 2020
Our Job No. 20693

04/02/2020

BARGHAUSEN CONSULTING ENGINEERS, INC.

18215 72ND AVENUE SOUTH KENT, WA 98032 P) 425-251-6222 F) 425-251-8782
BRANCH OFFICES: TUMWATER, WA KLAMATH FALLS, OR LONG BEACH, CA ROSEVILLE, CA SAN DIEGO, CA
barghausen.com

TECHNICAL INFORMATION REPORT

Barghausen Consulting Engineers, Inc.

Brown Bear - n=New Build

Issaquah, Washington

Our Job No. 20693

TABLE OF CONTENTS

1.0 PROJECT OVERVIEW

Figure 1.1 – Vicinity Map

2.0 CONDITIONS AND REQUIREMENTS SUMMARY

2.1 Analysis of the Minimum Requirements

3.0 EXISTING CONDITIONS SUMMARY

Figure 3.1 – Soil Survey Map

Figure 3.2 – Sensitive Areas Map

Figure 3.3 – Assessor's Map

Figure 3.4 – FEMA Map

4.0 OFF-SITE ANALYSIS REPORT

Figure 4.1 - Downstream Map

5.0 PERMANENT STORMWATER CONTROL PLAN

5.1 Existing Site Hydrology

Figure 5.1 – Pre-developed Basin Map

5.2 Developed Site Hydrology

Figure 5.2 – Developed Basin Map

5.3 Performance Standards and Goals

Figure 5.3 – Drainage Facility – Table 1-4 Water Quality Treatment Options

Figure 5.4 – Table 1-5 Requirements for On-Site Stormwater BMPs (MR#5)

5.4 Low Impact Development Features

5.5 Flow Control System

Figure 5.5 – Table 1-1 Project Screening for Stormwater Review

Figure 5.6 – Central Issaquah Area Alternative Flow Control Standard Map

Figure 5.7 – Detention Sizing Calculations

Figure 5.8 – Bypass Runoff Calculations

5.6 Water Quality System

Figure 5.9 - Contech WQ Basin Map

5.7 Conveyance System Analysis and Design

- 6.0 CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN
- 7.0 SPECIAL REPORTS AND STUDIES
- 8.0 OTHER PERMITS
- 9.0 OPERATIONS AND MAINTENANCE MANUAL
- 10.0 DECLARATION OF COVENANT FOR PRIVATELY MAINTAINED FLOW CONTROL AND TREATMENT FACILITIES
- 11.0 DECLARATION OF COVENANT FOR PRIVATELY MAINTAINED ON-SITE STORMWATER MANAGEMENT BMPs
- 12.0 BOND QUANTITIES WORKSHEET

Tab 1.0

1.0 PROJECT OVERVIEW


The proposed project site is located within Section 28, Township 24 North, Range 6 East of the Willamette Meridian with a total tax parcel area of 0.42 acres. More specifically, the site is located at 55 N.W. Gilman Blvd, Issaquah, WA 98027. The site consists of a single tax parcel with the number 8843500440. See Figure 1.1-Vicinity Map in this section for the location of the proposed project site.

The proposed development includes the construction of a 2,100-square-foot Brown Bear Car Wash, Auto Sentry Canopy, a covered trash enclosure, and replaced driving surface. The project will involve the removal of an existing gas station, and paved driving surface. The site is generally flat, with mild sloping down gradient from southeast to northwest. There do not appear to be any mapped or observed critical areas within the site's immediate vicinity. Existing site vegetation primarily consists of lawn grass, and landscaping shrubs.

The project site consists of a single Threshold Discharge Area and intends to match the existing drainage patterns on site. This project proposes more than 10,000 square feet of new and replaced impervious surface, and therefore all minimum requirements must be evaluated as specified in the flow chart (Figure 2) of this report. As part of the drainage requirements, the project intends to detain runoff generated from the site improvements to the maximum extent feasible, and comply with the Standard Flow Control Requirement per section 2.4.7 MR#7: Flow Control of the City of Issaquah 2017 Stormwater Design Manual Addendum. Additionally, this project proposes more than 5,000 square feet of new and replaced pollution generating hard surface to a commercial project site and therefore must provide enhanced water quality treatment per Section 2.4.6 MR#6: Runoff Treatment. This Stormwater Site Plan (TIR) will serve to address the drainage requirements contained within the City of Issaquah 2017 Stormwater Design Manual Addendum and the 2014 DOE Western Washington Stormwater Manual. Please see the remainder of this report for the project's design intent for mitigating any adverse impacts as a result of on-site improvements.

Figure 1.1 Vicinity Map





REFERENCE: Rand McNally (2019)

Scale:

Horizontal: N.T.S.

Vertical: N/A



**Barghausen
Consulting Engineers, Inc.**

18215 72nd Avenue South

Kent, WA 98032

425.251.6222

barghausen.com

For:

**Brown Bear Car Wash
Issaquah, Washington**

Title:

VICINITY MAP

Job Number

20693

DATE: 10/24/19

Tab 2.0

2.0 CONDITIONS AND REQUIREMENTS SUMMARY

This section contains the following information:

2.1 Analysis of the Minimum Requirements

2.1 Analysis of the Minimum Requirements

MINIMUM REQUIREMENTS	HOW PROJECT HAS ADDRESSED REQUIREMENT
No. 1: Preparation of Stormwater Site Plans	This Minimum Requirement has been fulfilled by the preparation and completion of this Stormwater Site Plan (TIR).
No. 2: Construction Stormwater Pollution Prevention (SWPP)	A completed Construction Stormwater Pollution Prevention Plan (SWPPP) will be submitted separately from, or together with, this report during Final Engineering Review.
No. 3: Source Control of Pollution	All known, available, and reasonable Source Control BMPs will be applied to this project in accordance with those applicable to a car wash project. At a minimum, the parking lot will be swept on a regular basis, and the owner will be educated about the proper use of pesticides and fertilizers. Per section 1.2.4 of the 2017 COI Stormwater Design Manual Addendum, the trash enclosure will be graded to prevent run-on from adjacent areas, and will drain directly to the sanitary sewer system. Additionally the trash enclosure will be constructed with a rooftop to minimize stormwater contact with trash and associated pollutants. Car washing areas will drain directly to the sewer system, and all chemicals will be stored within the carwash structure. Per S431 BMPs for Washing and Steam Cleaning Vehicles/Equipment/Building structures, all vehicle washing will take place within the proposed structure, and wash water will be collected by the carwash tunnel trench and discharged to the sanitary sewer system. Wash water will be isolated from stormwater runoff.
No. 4: Preservation of Natural Drainage Systems and Outfalls	The existing site appears to collect runoff into catch basins located on-site and discharge to the public stormwater conveyance system within N.W. Gilman Avenue. The proposed drainage design will collect on-site runoff and discharge stormwater to the same public stormwater conveyance system, thus preserving the existing drainage patterns.
No. 5: On-site Stormwater Management	This project triggers Minimum Requirements Nos. 1 through 9, and is defined as a redevelopment on a parcel inside the UGA; therefore, this project must either apply the Low Impacted Development Performance Standard and BMP T5.13: Post Construction Soil Quality and Depth; or evaluate the feasibility of the BMPs in List No. 2. This project will choose to evaluate the feasibility of BMPs from List No. 2 and apply them to the maximum extent feasible; however, it appears that all on-site stormwater management BMPs for proposed impervious surfaces are infeasible for this site.
No. 6: Runoff Treatment	This project proposes greater than 5,000 square feet of pollution generating hard surface, and must provide a water quality treatment facility. This site is defined as a commercial project and therefore, Enhanced Water Quality Treatment, and phosphorus removal must be provided. Runoff treatment will be provided by a Modular Wetland Water Quality System. This project is considered a high-use site, and will provide an on-line oil/water separator located downstream of the detention facility for oil control.

No. 7: Flow Control	This project proposes more than 10,000 square feet of new and replaced hard surface, and must provide flow control. A detention facility has been sized with WHHM2012 to match developed discharge durations to pre-developed durations for the range of pre-developed discharge rates from 50 percent of the 2-year recurrence interval peak flow up to the full 50-year peak flow.
No. 8: Wetlands Protection	There are no documented wetlands recorded on-site.
No. 9: Operation and Maintenance	The drainage facility for this project will be a private facility, owned and maintained by the owner. An Operation and Maintenance Manual will be provided in Section 9.0 of this Stormwater Site Plan during Final Engineering Review.

Tab 3.0




3.0 EXISTING CONDITIONS SUMMARY

The project site is located at the southwest corner of the intersection between N.W. Gilman Boulevard, and 1st Avenue N.W. Both 1st Avenue N.W., and Gilman are developed in their existing conditions. A paved alley runs along the site's east boundary. The property to the south is currently occupied by a commercial business. The majority of the site surface is covered by asphalt and concrete. Existing structures include a gas station canopy, fuel pumps, and tanks, and two existing structures. The existing impervious surfaces cover greater than 35 percent of the site's total area. The existing topography generally slopes from the southeast to the northwest at grades of 1 to 5 percent. The site soils have been identified as Everett Very Gravelly Sandy Loam, 0 to 8 percent slopes on the USDA Web Soil Survey Map. A soil investigation was conducted by Aspect Consulting, and provided information for this project's geotechnical report. The investigation determined the sites soils specifically consist of a mix between fill, and alluvium. The fill consists of "medium dense to very dense, moist, brown and gray, silty gravel with sand (GM)". The alluvium is described as dense to very dense, wet, brown and gray, gravel and sand with varying amount of silt (GM and SM). There do not appear to be any critical areas including wetlands or steep slopes within the immediate vicinity of the site; however, this site has been identified as being located within the Critical Aquifer Recharge Area Class 1 Zone and Sammamish Plateau Water District's Wellhead Protection Zone.

Figure 3.1

Soil Survey Map





REFERENCE: USDA, Natural Resources Conservation Service

LEGEND:

EvB = Everett very gravelly sandy loam, 0-8% slopes

HSG

A

Scale:

Horizontal: N.T.S.

Vertical: N/A

For:

Brown Bear Car Wash
Issaquah, Washington

Job Number

20693

Title:

SOIL SURVEY MAP

DATE: 10/24/19



**Barghausen
Consulting Engineers, Inc.**


18215 72nd Avenue South
Kent, WA 98032
425.251.6222

barghausen.com

Figure 3.2

Sensitive Areas Map





Legend

- | | |
|--|--------------------|
| Parcels | class 1 |
| Potential landslide hazard areas (2016, see explanation--->) | class 2 perennial |
| Potential steep slope hazard areas (2016, see explanation--->) | class 2 salmonid |
| Erosion hazard (1990 SAO) | class 3 |
| Seismic hazard (1990 SAO) | unclassified |
| Coal mine hazard (1990 SAO) | Wetland (1990 SAO) |

REFERENCE: King County iMAP (2019)

Scale:

Horizontal: N.T.S.

Vertical: N/A

For:

Brown Bear Car Wash
Issaquah, Washington

Job Number

20693

Title:

SENSITIVE AREAS
MAP

DATE: 10/24/19



**Barghausen
Consulting Engineers, Inc.**

18215 72nd Avenue South
Kent, WA 98032
425.251.6222

barghausen.com


Figure 3.3

Assessor's Map



Figure 3.4 FEMA Map





REFERENCE: Federal Emergency Management Agency (Portion of Map 53033C0691H, April 2005)

Scale:

Horizontal: N.T.S.

Vertical: N/A

For:

Brown Bear Car Wash
Issaquah, Washington

Job Number

20693

Title:

FEMA MAP

DATE: 10/24/19



**Barghausen
Consulting Engineers, Inc.**

18215 72nd Avenue South

Kent, WA 98032

425.251.6222

barghausen.com

Tab 4.0

4.0 OFF-SITE ANALYSIS REPORT

The immediate upstream basin of the site consists of a single property to the south, and both 1st Avenue N.W. to the west of the site, and a paved alley to the east of the site. Runoff from these upstream surfaces appears to collect in the conveyance systems within 1st Avenue N.W. and the alley. It is not anticipated that runoff from the proposed development will contribute a negative impact on upstream properties.


The immediate downstream basin of the site appears to be confined to N.W. Gilman Boulevard. Runoff from N.W. Gilman Boulevard is collected into catch basins and is conveyed northwest. It appears that stormwater within this conveyance system ultimately discharges to Issaquah Creek, before reaching Lake Sammamish. This project intends to detain stormwater runoff to the maximum extent feasible to meet flow control standards specified in MR#7, and proposes a net reduction of impervious surface. Additionally this project intends to provide enhanced stormwater quality treatment, and is not anticipated to create a negative impact on the downstream basin or receiving freshwater bodies.

Figure 4.1

Downstream Map



Downstream Map



Tab 5.0

5.0 PERMANENT STORMWATER CONTROL PLAN

This section contains the following information:

- 5.1 Existing Site Hydrology
- 5.2 Developed Site Hydrology
- 5.3 Performance Standards and Goals
- 5.4 Low Impact Development Features
- 5.5 Flow Control System
- 5.6 Water Quality System
- 5.7 Conveyance System Analysis and Design

5.1 Existing Site Hydrology

The existing site collects runoff into catch basins located on-site and within adjacent public right-of-ways. The existing surface is primarily impervious, consisting of rooftops, concrete, and asphalt. Limited vegetation exists on-site.

Predeveloped Basins

The predeveloped basin, tributary to the site discharge location, can be broken down as follows:

Impervious	Pervious	Total Area
0.443 Ac	0.056 Ac	0.499 Ac

Areas include both the tax parcel surfaces, and surfaces within the public ROW




For a detailed explanation of the procedures used for the sizing of the proposed drainage facility please reference Section 5.4 of this report.



Figure 5.1 Pre-developed Basin Map



PRE-DEVELOPED BASIN AREAS:

EXISTING IMPERVIOUS/PERVIOUS AREAS

BUILDINGS:	4,382 SF (0.100 AC)	
DRIVING SURFACE, CONC. WALKWAYS, CURBS:	14,893 SF (0.342 AC)	
TOTAL EXISTING IMPERVIOUS:	19,275 SF (0.442 AC)	
LANDSCAPE:	2,449 SF (0.055 AC)	
TOTAL BASIN AREA:	21,724 SF (0.499 AC)	




PRE-DEVELOPED BASIN MAP

FOR

BROWN BEAR CAR WASH

SE 1/4 OF NE 1/4 OF SEC. 28, TWN. 24 N, RGE. 6 E, W.M.
CITY OF ISSAQUAH, KING COUNTY, WASHINGTON



2	4/3/2020	ADW / AEM	CRJ	CRJ	PER CITY REVIEW COMMENTS RECEIVED 02/19/2020
1	11/15/19	ADW / AEM	CRJ	CRJ	LAND USE SUBMITTAL

No.	Date	By	Chd.	Appr.	Revision
-----	------	----	------	-------	----------


Title:
PRE-DEVELOPED BASIN MAP
BROWN BEAR CAR WASH
55 NW GILMAN BLVD.
ISSAQUAH, WA

For:
CAR WASH ENTERPRISES, INC.
3977 LEARY WAY NW
SEATTLE, WASHINGTON 98107

4/3/2020

Designed	ADW	Drawn	ADW	Checked	AEM	Approved	CRJ	Date	11/15/19
Scale:									
Horizontal									1" = 10'
Vertical									NA

Barghausen Consulting Engineers, Inc.
18215 72nd Avenue South
Kent, WA 98032
425.251.6222 barghausen.com



Know what's below.
Call before you dig.
Dial 811

Job Number
20693

Sheet
1 of **1**

5.2 Developed Site Hydrology

Narrative

Developed Basins

The developed basin, tributary to the site discharge location, can be broken down as follows:

Detained Basin

Impervious	Pervious	Total Area
0.303 Ac	0.120 Ac	0.423 Ac

Bypass Basin

Impervious	Pervious	Total Area
0.074 Ac	0.002 Ac	0.076 Ac

A detailed report on the procedures used for the sizing of the proposed combination detention and water quality pond is provided in Section 5.4 of this report.

Figure 5.2

Developed Basin Map



TOTAL PROJECT BASIN AREA: 18,431 SF + 3,293 SF = 21,724 SF (0.499 AC)

1ST PL NW

425.257.6222
barghausen.com

For:

Title:

DEVELOPED BASIN MAP
BROWN BEAR CAR WASH
55 NW GILMAN BLVD.
ISSAQUAH, WA

No.	Date	By	Appr.	Revision
1	11/15/19	ADW AEM	CRJ	LAND USE SUBMITTAL
2	4/3/2020	ADW AEM	CRJ	PER CITY REVIEW COMMENTS RECEIVED 02/19/2020

4/3/2020

scale:

Horizontal
1" = 10'

Vertical
NA

Designed ADW
 Drawn ADW
 Checked AEM
 Approved CRJ
 Date 11/15/19

20693

Sheet 1 of 1



Know what's **below**.
Call before you dig.
 Dial 811

P:\20000s\20693\exhibit\20693-Developed Basin Map.dwg 4/2/2020 1:04 PM AWHITE

5.3 Performance Standards and Goals

This project proposes to create more than 10,000 square feet of new and replaced impervious surface within a threshold discharge area, and is located outside the City of Issaquah Alternative Flow Control Drainage Basin. This project site's existing surface contains greater than 35 percent impervious surface coverage and is therefore defined as a redevelopment project. The anticipated increase value of the site improvements will likely be greater than 50 percent of the value of existing site improvements; therefore, all new and replaced hard surfaces are considered targeted surfaces. Additionally, the pre-developed condition of the site must be modeled as forested for the purpose of flow control calculations. This project will provide flow control to "Match developed discharge durations to pre-developed duration for the range of predeveloped discharge rates from 50 percent of the 2-year peak flow up to the full 50-year peak flow" per Minimum Requirement No. 7.

Water quality treatment must also be provided per Minimum Requirement No. 6, as this project proposes greater than 5,000 square feet pollution generating hard surface. This site is a commercial project site and is an anticipated high use site, therefore Enhanced treatment must be provided. This project will propose a Bio clean Environmental MWS-Linear Modular Wetland system that will treat stormwater runoff downstream of the proposed detention facility.

Figure 5.3

Drainage Facility

for pretreatment, hydraulic profile, design treatment flow rates, flow bypass, and other criteria.

Table 1-4 lists GULD-approved technologies for pre-treatment, basic, enhance, and phosphorus treatment. This list is also contained in the Approved Materials List and will be updated periodically. Basic treatment and pre-treatment is used prior to infiltration or as part of treatment train (see design manual).

TABLE 1-4 WATER QUALITY TREATMENT OPTIONS				
Product	Pre-Treat	Basic	Enhanced	Phosp.
EMERGING TECHNOLOGIES				
AquaShield Aqua-Swirl System	X			
Baysaver BayFilter®		X		
Contech CDS™ Stormwater Treatment System	X			
WSDOT Compost-Amended Biofiltration Swale		X	X	
Hydro International Downstream Defender	X			
Watertechtonics ecoStorm plus		X		
Contech Filterra® Bioscape™		X	X	X
Contech Filterra® System		X	X	X
Oldcastle FloGard Perk Filter®		X		X
WSDOT Media Filter Drain		X	X	X
Contech Media Filtration System		X		
Bio Clean Environmental MWS-Linear Modular Wetland		X	X	X
Imbrium Systems Stormceptor	X			
Contech StormFilter -PhosphoSorb Media at 1.67 gpm/sq ft		X		X
Contech Stormfilter using ZPG Media		X		
Contech Vortechs System	X			
STORMWATER DESIGN MANUAL				
Infiltration (with pretreatment)		X	X	X
Large sand filter ¹		X	X	X
Large wet pond		X		X
Two-facility treatment train (see manual) ²		X	X	X

¹Private development only. Sand filters not accepted as a City-owned facility.

²Requires basic or linear sand filter as part of the treatment train, also not accepted as a City-owned facility.

Figure 5.4
Table 1-5
Requirements for
On-Site Stormwater
BMPs

TABLE 1-5 REQUIREMENTS FOR ON-SITE STORMWATER BMPs (MR#5)

Surface	How Evaluated	BMPs to be Evaluated for Feasibility		General Criteria ^a
		Projects that trigger MR#1-MR#5	Projects that Trigger MR#6-MR#9	
Lawn/ Landscaped Areas	Required in all projects.	1. Post-Construction Soil Quality and Depth (BMP T5.13; IMC 18.12.140)		De-compact and add topsoil meeting pH and organic criteria to depth of 8 inches.
Roofs	Use BMPs that are determined to be feasible, evaluated in order listed, until full BMP criteria is met.	2a. Full Dispersion (BMP T5.30), <u>or</u> Downspout Full Infiltration Systems (BMP T5.10A).		Full dispersion requires large native growth area: 6.5 times area of roof draining to it. Downspout infiltration requires less area but is subject to soil conditions.
		2b. Rain Gardens (BMP T5.14A), <u>or</u> Bioretention.	Same as MR#1-MR#5 except Bioretention in place of rain gardens.	Area of rain garden or bioretention to be 5% of roof area draining to it, at depth of 6-12 inches. Bioretention adds engineering criteria on design infiltration rate.
		2c. Downspout Dispersion Systems (BMP T5.10B)		Used if dispersion area is moderate (25-50 ft length) using splash blocks or gravel-filled trenches
		2d. Perforated Stub-out Connections (BMP T5.10C)		Used if dispersion area is minimal (<25 ft length) using perforated pipe in 24" wide gravel trench
Other Hard Surfaces (e.g., parking lots, sidewalks)	Use BMPs that are determined to be feasible, evaluated in order listed, until full BMP criteria is met.	3a. Full Dispersion (BMP T5.30)		Full Dispersion: see #2a above.
		3b. Permeable pavement (BMP T5.15), <u>or</u> Rain Gardens (BMP T5.14A)	Same as MR#1-MR#5 except Bioretention in place of rain gardens.	Permeable pavement: All surfaces, except high use, roads >400 ADT, and other infeasibility criteria. Rain gardens/bioretention: see #2b above.
		3c. Sheet Flow Dispersion (BMP T5.12), or Concentrated Flow Dispersion (BMP T5.11)		Sheet flow: min 10 ft or larger vegetated buffer next to parking lot or road. Concentrated flow dispersion requires 50 ft flow path and is limited to 700 sf of hard surface.

^a This is a generalized summary only, and does not reflect the BMP infeasibility criteria or competing needs assessment that may apply to the project and site. See BMP sheets in Ecology Manual for complete criteria.

5.4 Low Impact Development Features

This project triggers Minimum Requirements Nos. 1 through 9 and must either use on-site stormwater management BMPs from List No. 2, or demonstrate compliance with the LID Performance Standard and BMP T5.13. This project will choose to evaluate the feasibility of on-site stormwater management BMPs from List No. 2.

Lawn and Landscaped Areas

1. Soil preservation and Amendment BMP in Volume III, Section 3.1.

Feasible: Post Construction Soil Quality and Depth in accordance with BMP T5.13 in Chapter 5 Volume V of the SWMMWW will be applied to all proposed landscaping areas.

Roofs:

1. Full Dispersion in accordance with BMP T5.30 in Chapter 5 of Volume V of the SWMMWW, or Downspout Full Infiltration Systems in accordance with BMP T5.10A in Section 3.1.1 of Volume III of the SWMMWW.

Infeasible: This project will not preserve 65 percent of the site area as forest or native vegetation. Additionally, infiltration is infeasible for this project due to the project being located within a CARA Class 1, and wellhead protection zone.

2. Bioretention (See Chapter 7 of Volume V of the SWMMWW) facilities that have a minimum horizontally projected surface area below the overflow, which is at least 5 percent of the total surface area draining to it.

Infeasible: Bioretention is infeasible due to the infeasibility of on-site infiltration. The site is located within a CARA Class 1, and a wellhead protection Zone.

3. Downspout Dispersion Systems in accordance with BMP T5.10B in Section 3.1.2, Volume III, of the SWMMWW.

Infeasible: Downspout dispersion systems are infeasible due to the lack of available vegetated area and flow path space.

4. Perforated Stub-out Connections in accordance with BMP T5.10C in Section 3.1.3, Volume III, of the SWMMWW.

Infeasible: Perforated Stub-out Connections are infeasible. All rooftop runoff is proposed to be collected and discharge to a stormwater detention facility designed to meet Minimum Requirement No. 7 of Flow Control Requirements.

Other Hard Surfaces:

1. Full Dispersion in accordance with BMP T5.30 in Chapter, Volume V, of the SWMMWW.

Infeasible: This project will not preserve 65 percent of the site area as forest or native vegetation.

2. Permeable Pavement No. 2 is in accordance with BMP T5.15 in Chapter 5, Volume V, of the SWMMWW.

Infeasible: This site is defined as high use, and therefore does not require the evaluation of permeable pavement. Additionally, this site is not allowed to use infiltration BMPs as it is located within a CARA.

3. Bioretention (See Chapter 7, Volume V of the SWMMWW) facilities that have a minimum horizontally projected surface area below the overflow which is at least 5 percent of the total surface area draining to it.

Infeasible: Bioretention is infeasible due to the infeasibility of on-site infiltration. The site is located within a CARA Class 1, and wellhead protection Zone.

4. Sheet Flow Dispersion in accordance with BMP T5.12, or Concentrated Flow Dispersion in accordance with BMP T5.11 in Chapter 5, Volume V, of the SWMMWW.

Infeasible: The site lacks the available vegetated flow path space for sheet flow dispersion per BMP T5.12, or concentrated flow dispersion per BMP T5.11.

5.5 Flow Control System

This site proposes greater than 10,000 square feet of new and replaced impervious surface and will provide flow control such that "Stormwater discharges shall match developed discharge durations to pre-developed durations for the range of pre-developed discharge rates from 50 percent of the 2-year peak flow up to the full 50-year peak flow."

The site is located within a CARA Class 1 and is not allowed to infiltrate stormwater runoff. A detention vault has been proposed to meet the required flow control standard.

The proposed stormwater detention vault has been sized using WWHM2012.

The pre-developed condition has been modeled as a forested land cover.

The developed condition models all proposed rooftop areas, and other hard surfaces that will drain to the detention facility. Proposed pervious areas will implement BMP T5.13: Post Construction Soil Quality and Depth have been modeled as pasture as allowed by SWMMWW Volume III Appendix C.

Bypass Area

Improvements within the public right-of-way will bypass the detention system, as they cannot be feasibly isolated from the surrounding street surfaces, and collected. WWHM2012 calculation indicate that flow rate durations of the bypass area alone closely match the pre-developed flow rate durations for the entire site.; therefore, it will not be possible or feasible to design a detention system that will meet the flow control standard if the bypass area is modeled as un-detained runoff. Per the 2014 DOE SWMMWW, Volume III – Appendix B, the following conditions for the bypass area must be met:

1. *Runoff from both the bypass area and the flow control facility converges within a quarter-mile downstream of the project site discharge point.*

Response: Runoff from the detained area will discharge to stormwater conveyance that collects runoff from the bypass areas immediately adjacent to the site. The location of convergence is approximately 40 feet downstream of the project site.

2. *The flow control facility is designed to compensate for the uncontrolled bypass area such that the net effect at the point of convergence downstream is the same with or without bypass.*

Response: The flow control facility has been sized to compensate for the uncontrolled bypass area. The detention vault is sized to accept runoff from an area equivalent to the bypass area while meeting the flow control standard. Therefore, the net effect of this compensation will allow the site to meet the flow control duration standard weather the site is modeled with or without the bypass area.

3. *The 100-year peak discharge from the bypass area will not exceed 0.4 cfs*

Response: The 100-Year peak discharge rate from the bypass area does not exceed 0.4 cfs. WWHM2012 calculations of the bypass area flow frequency rates are included in this report.

4. *Runoff from the bypass area will not create a significant adverse impact to downstream drainage systems or properties.*

Response: The existing conditions of the bypass area consist of an almost entirely impervious area. Runoff characteristics within the bypass area will remain relatively

unchanged with the proposed developments, and therefore it is anticipated that the bypass area will not create an observable adverse impact to downstream drainage systems or properties.

5. *Water quality requirements applicable to the bypass area are met.*

Response: The pollution generating hard surface area of the bypass area is approximately 1,036 square feet. Due to site constraints, treatment of an area greater than or equal to the proposed pollution generating hard surfaces within the ROW is proposed to be achieved with a Contech Stormfilter Concrete Catch Basin.

Pump Design

Due to the shallow depth of the downstream conveyance system, this project will require a pump system to be placed downstream of the flow control facility. The pump system has been designed to activate when water within the pump basin reaches a depth equal to IE of the pump basin's inlet pipe, and provides a discharge rate greater than or equal to the anticipated 100-year mitigated flow rate to ensure the prevention of a backwater condition within the vault, and water quality facilities. This will also ensure that gravity flow is maintained between the outlet of the vault and the pump basin. By maintaining gravity flow between the detention facility and the pump basin, the hydraulic residence time of on-site runoff within the detention vault remains equivalent between the proposed pump system, and a system that would depend entirely on gravity flows; therefore, the quantity of stormwater discharge during the pump activation timeframe will be equivalent to the quantity of stormwater discharged through a gravity system during the full pump cycle timeframe.

Figure 5.5
Table 1-1 Project
Screening for
Stormwater Review

Table 1-1 PROJECT SCREENING FOR STORMWATER REVIEW							
Project Type ^b	Screening Thresholds ^a			Minimum Requirements ^a			
	Hard Surfaces		Land Clearing	MR #1-5	MR #6-9	Stormwater Facility Target Surfaces ^d	Pre-Dev Cond.
1. TESC Only	<2000 SF new plus replaced hard surfaces	or	<7000 SF land disturbance	MR #2 – Construction Stormwater Pollution Prevention Plan			
2. New Development – All projects^c	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New and replaced</u> hard surfaces	Forested
3a. Redevelopment - Value of proposed improvements is <50% of value of existing site improvements^c	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New</u> hard surfaces only	Forested
3b. Redevelopment - Value of proposed improvements is >50% of value of existing site improvements^c	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New and replaced</u> hard surfaces	Forested
4a. Transportation redevelopment - New hard surfaces add <50% to existing hard surfaces	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New</u> hard surfaces only	Forested
4b. Transportation redevelopment - New hard surfaces add >50% to existing hard surfaces	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New and replaced</u> hard surfaces	Forested
5. Central Issaquah Alternative Flow Control Area (see Figure 2-5) – All projects	2000-5000 SF new plus replaced hard surfaces	or	7000-32,670 SF land disturbance	✓		--	--
	>5000 SF new plus replaced hard surfaces	or	>32,670 SF land disturbance	✓	✓	<u>New</u> hard surfaces only	Existing

^aSee Chapter 2 for requirements, following the flow charts in Figures 2-4 and 2-4 and referring to Minimum Requirements for specific criteria.

^bSee Chapter 2.1 for additional exemptions.

^cNew Development are sites with <35% existing impervious coverage; Redevelopment are sites with >35% existing impervious coverage.

^dStormwater Facility Target Surfaces: for flow control and water quality treatment. Onsite Stormwater BMPs required under MR #5.

Figure 5.6
Central Issaquah Area
Alternative Flow
Control Standard Map

Figure 2-5. Central Issaquah Area Alternative Flow Control Standard Map




Figure 5.7

Detention Sizing Calculations

WWHM2012
PROJECT REPORT

General Model Information

Project Name: 20693-Detention 2020-4-1
Site Name: Brown Bear Car Wash
Site Address: 55 NW Gilman BLVD
City: Issaquah, WA
Report Date: 4/1/2020
Gage: Seatac
Data Start: 1948/10/01
Data End: 2009/09/30
Timestep: 15 Minute
Precip Scale: 1.333
Version Date: 2019/09/13
Version: 4.2.17

POC Thresholds

Low Flow Threshold for POC1:	50 Percent of the 2 Year
High Flow Threshold for POC1:	50 Year

Landuse Basin Data

Predeveloped Land Use

Basin 1

Bypass: No

GroundWater: No

Pervious Land Use acre
C, Forest, Flat 0.499

Pervious Total 0.499

Impervious Land Use acre

Impervious Total 0

Basin Total 0.499

Element Flows To:		
Surface	Interflow	Groundwater

Mitigated Land Use

Basin 1

Bypass:	No
GroundWater:	No
Pervious Land Use	acre
C, Pasture, Flat	0.122
Pervious Total	0.122
Impervious Land Use	acre
ROADS FLAT	0.311
ROOF TOPS FLAT	0.066
Impervious Total	0.377
Basin Total	0.499

Element Flows To:		
Surface	Interflow	Groundwater
Vault 1	Vault 1	

Routing Elements

Predeveloped Routing

Mitigated Routing

Vault 1

Width: 41.5 ft.
Length: 41.5 ft.
Depth: 7 ft.
Discharge Structure
Riser Height: 6 ft.
Riser Diameter: 18 in.
Orifice 1 Diameter: 0.45 in. Elevation: 0 ft.
Orifice 2 Diameter: 0.8 in. Elevation: 4.002 ft.
Orifice 3 Diameter: 0.59 in. Elevation: 5.03375 ft.
Element Flows To:
Outlet 1 Outlet 2


Vault Hydraulic Table

Stage(feet)	Area(ac.)	Volume(ac-ft.)	Discharge(cfs)	Infilt(cfs)
0.0000	0.039	0.000	0.000	0.000
0.0778	0.039	0.003	0.001	0.000
0.1556	0.039	0.006	0.002	0.000
0.2333	0.039	0.009	0.002	0.000
0.3111	0.039	0.012	0.003	0.000
0.3889	0.039	0.015	0.003	0.000
0.4667	0.039	0.018	0.003	0.000
0.5444	0.039	0.021	0.004	0.000
0.6222	0.039	0.024	0.004	0.000
0.7000	0.039	0.027	0.004	0.000
0.7778	0.039	0.030	0.004	0.000
0.8556	0.039	0.033	0.005	0.000
0.9333	0.039	0.036	0.005	0.000
1.0111	0.039	0.040	0.005	0.000
1.0889	0.039	0.043	0.005	0.000
1.1667	0.039	0.046	0.005	0.000
1.2444	0.039	0.049	0.006	0.000
1.3222	0.039	0.052	0.006	0.000
1.4000	0.039	0.055	0.006	0.000
1.4778	0.039	0.058	0.006	0.000
1.5556	0.039	0.061	0.006	0.000
1.6333	0.039	0.064	0.007	0.000
1.7111	0.039	0.067	0.007	0.000
1.7889	0.039	0.070	0.007	0.000
1.8667	0.039	0.073	0.007	0.000
1.9444	0.039	0.076	0.007	0.000
2.0222	0.039	0.080	0.007	0.000
2.1000	0.039	0.083	0.008	0.000
2.1778	0.039	0.086	0.008	0.000
2.2556	0.039	0.089	0.008	0.000
2.3333	0.039	0.092	0.008	0.000
2.4111	0.039	0.095	0.008	0.000
2.4889	0.039	0.098	0.008	0.000
2.5667	0.039	0.101	0.008	0.000
2.6444	0.039	0.104	0.008	0.000
2.7222	0.039	0.107	0.009	0.000
2.8000	0.039	0.110	0.009	0.000
2.8778	0.039	0.113	0.009	0.000


2.9556	0.039	0.116	0.009	0.000
3.0333	0.039	0.119	0.009	0.000
3.1111	0.039	0.123	0.009	0.000
3.1889	0.039	0.126	0.009	0.000
3.2667	0.039	0.129	0.009	0.000
3.3444	0.039	0.132	0.010	0.000
3.4222	0.039	0.135	0.010	0.000
3.5000	0.039	0.138	0.010	0.000
3.5778	0.039	0.141	0.010	0.000
3.6556	0.039	0.144	0.010	0.000
3.7333	0.039	0.147	0.010	0.000
3.8111	0.039	0.150	0.010	0.000
3.8889	0.039	0.153	0.010	0.000
3.9667	0.039	0.156	0.010	0.000
4.0444	0.039	0.159	0.014	0.000
4.1222	0.039	0.163	0.017	0.000
4.2000	0.039	0.166	0.019	0.000
4.2778	0.039	0.169	0.020	0.000
4.3556	0.039	0.172	0.021	0.000
4.4333	0.039	0.175	0.023	0.000
4.5111	0.039	0.178	0.024	0.000
4.5889	0.039	0.181	0.025	0.000
4.6667	0.039	0.184	0.026	0.000
4.7444	0.039	0.187	0.026	0.000
4.8222	0.039	0.190	0.027	0.000
4.9000	0.039	0.193	0.028	0.000
4.9778	0.039	0.196	0.029	0.000
5.0556	0.039	0.199	0.031	0.000
5.1333	0.039	0.203	0.033	0.000
5.2111	0.039	0.206	0.035	0.000
5.2889	0.039	0.209	0.037	0.000
5.3667	0.039	0.212	0.038	0.000
5.4444	0.039	0.215	0.039	0.000
5.5222	0.039	0.218	0.040	0.000
5.6000	0.039	0.221	0.042	0.000
5.6778	0.039	0.224	0.043	0.000
5.7556	0.039	0.227	0.044	0.000
5.8333	0.039	0.230	0.045	0.000
5.9111	0.039	0.233	0.046	0.000
5.9889	0.039	0.236	0.047	0.000
6.0667	0.039	0.239	0.321	0.000
6.1444	0.039	0.242	0.918	0.000
6.2222	0.039	0.246	1.686	0.000
6.3000	0.039	0.249	2.552	0.000
6.3778	0.039	0.252	3.437	0.000
6.4556	0.039	0.255	4.268	0.000
6.5333	0.039	0.258	4.977	0.000
6.6111	0.039	0.261	5.522	0.000
6.6889	0.039	0.264	5.903	0.000
6.7667	0.039	0.267	6.260	0.000
6.8444	0.039	0.270	6.568	0.000
6.9222	0.039	0.273	6.862	0.000
7.0000	0.039	0.276	7.144	0.000
7.0778	0.039	0.279	7.415	0.000
7.1556	0.000	0.000	7.677	0.000

Analysis Results

POC 1



+ Predeveloped x Mitigated



Predeveloped Landuse Totals for POC #1

Total Pervious Area: 0.499
Total Impervious Area: 0

Mitigated Landuse Totals for POC #1

Total Pervious Area: 0.122
Total Impervious Area: 0.377

Flow Frequency Method: Log Pearson Type III 17B

Flow Frequency Return Periods for Predeveloped. POC #1

Return Period	Flow(cfs)
2 year	0.02584
5 year	0.044242
10 year	0.059653
25 year	0.083179
50 year	0.103896
100 year	0.127561

Flow Frequency Return Periods for Mitigated. POC #1

Return Period	Flow(cfs)
2 year	0.012515
5 year	0.020665
10 year	0.027759
25 year	0.039021
50 year	0.049334
100 year	0.061525

Annual Peaks

Annual Peaks for Predeveloped and Mitigated. POC #1

Year	Predeveloped	Mitigated
1949	0.037	0.009
1950	0.042	0.011
1951	0.048	0.039
1952	0.016	0.008
1953	0.014	0.010
1954	0.020	0.009
1955	0.031	0.009
1956	0.028	0.022
1957	0.025	0.009
1958	0.023	0.010

1959	0.019	0.009
1960	0.042	0.028
1961	0.019	0.011
1962	0.013	0.008
1963	0.019	0.010
1964	0.025	0.011
1965	0.021	0.018
1966	0.016	0.010
1967	0.043	0.010
1968	0.022	0.010
1969	0.022	0.009
1970	0.019	0.010
1971	0.026	0.010
1972	0.037	0.030
1973	0.018	0.018
1974	0.024	0.010
1975	0.032	0.009
1976	0.022	0.010
1977	0.015	0.008
1978	0.018	0.010
1979	0.011	0.007
1980	0.070	0.031
1981	0.016	0.010
1982	0.045	0.023
1983	0.026	0.010
1984	0.016	0.008
1985	0.010	0.008
1986	0.040	0.011
1987	0.038	0.026
1988	0.017	0.009
1989	0.010	0.008
1990	0.141	0.029
1991	0.057	0.027
1992	0.021	0.010
1993	0.019	0.008
1994	0.009	0.007
1995	0.025	0.011
1996	0.064	0.037
1997	0.046	0.036
1998	0.022	0.008
1999	0.085	0.028
2000	0.018	0.010
2001	0.006	0.007
2002	0.032	0.014
2003	0.043	0.009
2004	0.045	0.038
2005	0.028	0.010
2006	0.028	0.022
2007	0.113	0.062
2008	0.091	0.034
2009	0.040	0.018

Ranked Annual Peaks

Ranked Annual Peaks for Predeveloped and Mitigated. POC #1

Rank	Predeveloped	Mitigated
1	0.1408	0.0624
2	0.1127	0.0391
3	0.0908	0.0384

4	0.0852	0.0369
5	0.0699	0.0356
6	0.0641	0.0344
7	0.0570	0.0308
8	0.0478	0.0295
9	0.0465	0.0286
10	0.0451	0.0285
11	0.0445	0.0279
12	0.0427	0.0272
13	0.0426	0.0262
14	0.0420	0.0235
15	0.0417	0.0222
16	0.0401	0.0220
17	0.0397	0.0185
18	0.0383	0.0181
19	0.0375	0.0179
20	0.0375	0.0143
21	0.0322	0.0109
22	0.0315	0.0109
23	0.0310	0.0107
24	0.0279	0.0106
25	0.0276	0.0105
26	0.0275	0.0105
27	0.0261	0.0104
28	0.0259	0.0104
29	0.0254	0.0104
30	0.0252	0.0102
31	0.0250	0.0100
32	0.0241	0.0100
33	0.0229	0.0100
34	0.0224	0.0099
35	0.0224	0.0099
36	0.0222	0.0098
37	0.0216	0.0097
38	0.0210	0.0096
39	0.0209	0.0096
40	0.0201	0.0096
41	0.0195	0.0095
42	0.0192	0.0095
43	0.0190	0.0095
44	0.0189	0.0093
45	0.0188	0.0093
46	0.0182	0.0092
47	0.0181	0.0090
48	0.0176	0.0089
49	0.0165	0.0088
50	0.0164	0.0088
51	0.0163	0.0084
52	0.0158	0.0083
53	0.0155	0.0082
54	0.0155	0.0082
55	0.0142	0.0081
56	0.0132	0.0080
57	0.0113	0.0079
58	0.0104	0.0079
59	0.0100	0.0074
60	0.0090	0.0073
61	0.0058	0.0069

Duration Flows

The Facility PASSED

Flow(cfs)	Predev	Mit	Percentage	Pass/Fail
0.0129	16358	4327	26	Pass
0.0138	13956	4122	29	Pass
0.0148	11777	3925	33	Pass
0.0157	9989	3664	36	Pass
0.0166	8470	3416	40	Pass
0.0175	7328	3183	43	Pass
0.0184	6297	2937	46	Pass
0.0194	5461	2723	49	Pass
0.0203	4836	2494	51	Pass
0.0212	4278	2276	53	Pass
0.0221	3809	2023	53	Pass
0.0230	3343	1783	53	Pass
0.0239	2947	1547	52	Pass
0.0249	2592	1358	52	Pass
0.0258	2284	1169	51	Pass
0.0267	2016	962	47	Pass
0.0276	1807	792	43	Pass
0.0285	1604	579	36	Pass
0.0295	1379	440	31	Pass
0.0304	1222	368	30	Pass
0.0313	1110	332	29	Pass
0.0322	1004	305	30	Pass
0.0331	911	280	30	Pass
0.0341	814	253	31	Pass
0.0350	730	219	30	Pass
0.0359	659	187	28	Pass
0.0368	542	159	29	Pass
0.0377	450	132	29	Pass
0.0387	389	98	25	Pass
0.0396	332	83	25	Pass
0.0405	260	70	26	Pass
0.0414	215	62	28	Pass
0.0423	177	56	31	Pass
0.0432	141	49	34	Pass
0.0442	116	43	37	Pass
0.0451	94	36	38	Pass
0.0460	79	22	27	Pass
0.0469	69	13	18	Pass
0.0478	57	7	12	Pass
0.0488	52	6	11	Pass
0.0497	48	6	12	Pass
0.0506	44	5	11	Pass
0.0515	36	5	13	Pass
0.0524	31	4	12	Pass
0.0534	27	3	11	Pass
0.0543	21	2	9	Pass
0.0552	16	2	12	Pass
0.0561	15	2	13	Pass
0.0570	11	2	18	Pass
0.0579	11	2	18	Pass
0.0589	11	2	18	Pass
0.0598	10	2	20	Pass
0.0607	10	1	10	Pass

0.0616	10	1	10	Pass
0.0625	10	0	0	Pass
0.0635	10	0	0	Pass
0.0644	9	0	0	Pass
0.0653	9	0	0	Pass
0.0662	9	0	0	Pass
0.0671	9	0	0	Pass
0.0681	9	0	0	Pass
0.0690	9	0	0	Pass
0.0699	8	0	0	Pass
0.0708	8	0	0	Pass
0.0717	7	0	0	Pass
0.0727	7	0	0	Pass
0.0736	7	0	0	Pass
0.0745	7	0	0	Pass
0.0754	7	0	0	Pass
0.0763	6	0	0	Pass
0.0772	6	0	0	Pass
0.0782	6	0	0	Pass
0.0791	6	0	0	Pass
0.0800	6	0	0	Pass
0.0809	6	0	0	Pass
0.0818	6	0	0	Pass
0.0828	6	0	0	Pass
0.0837	5	0	0	Pass
0.0846	5	0	0	Pass
0.0855	4	0	0	Pass
0.0864	4	0	0	Pass
0.0874	4	0	0	Pass
0.0883	4	0	0	Pass
0.0892	3	0	0	Pass
0.0901	3	0	0	Pass
0.0910	2	0	0	Pass
0.0919	2	0	0	Pass
0.0929	2	0	0	Pass
0.0938	2	0	0	Pass
0.0947	2	0	0	Pass
0.0956	2	0	0	Pass
0.0965	2	0	0	Pass
0.0975	2	0	0	Pass
0.0984	2	0	0	Pass
0.0993	2	0	0	Pass
0.1002	2	0	0	Pass
0.1011	2	0	0	Pass
0.1021	2	0	0	Pass
0.1030	2	0	0	Pass
0.1039	2	0	0	Pass

Water Quality

Water Quality BMP Flow and Volume for POC #1

On-line facility volume: 0 acre-feet

On-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

Off-line facility target flow: 0 cfs.

Adjusted for 15 min: 0 cfs.

LID Report

LID Technique	Used for Treatment ?	Total Volume Needs Treatment (ac-ft)	Volume Through Facility (ac-ft)	Infiltration Volume (ac-ft)	Cumulative Volume Infiltration Credit	Percent Volume Infiltrated	Water Quality	Percent Water Quality Treated	Comment
Vault 1 POC	<input type="checkbox"/>	86.37			<input type="checkbox"/>	0.00			
Total Volume Infiltrated		86.37	0.00	0.00		0.00	0.00	0%	No Treat. Credit
Compliance with LID Standard 8% of 2-yr to 50% of 2-yr									Duration Analysis Result = Failed

Model Default Modifications

Total of 0 changes have been made.

PERLND Changes


No PERLND changes have been made.

IMPLND Changes


No IMPLND changes have been made.

Appendix

Predeveloped Schematic



Mitigated Schematic



Disclaimer


Legal Notice


This program and accompanying documentation are provided 'as-is' without warranty of any kind. The entire risk regarding the performance and results of this program is assumed by End User. Clear Creek Solutions Inc. and the governmental licensee or sublicensees disclaim all warranties, either expressed or implied, including but not limited to implied warranties of program and accompanying documentation. In no event shall Clear Creek Solutions Inc. be liable for any damages whatsoever (including without limitation to damages for loss of business profits, loss of business information, business interruption, and the like) arising out of the use of, or inability to use this program even if Clear Creek Solutions Inc. or their authorized representatives have been advised of the possibility of such damages. Software Copyright © by : Clear Creek Solutions, Inc. 2005-2020; All Rights Reserved.

Clear Creek Solutions, Inc.
6200 Capitol Blvd. Ste F
Olympia, WA. 98501
Toll Free 1(866)943-0304
Local (360)943-0304

www.clearcreeksolutions.com

Figure 5.8 Bypass Runoff Calculations





Bypass Areas alone matches entire pre-developed site. Cannot model as "bypass" in detention calcs.

5.6 Water Quality System



The project is defined as a commercial project, on a high use site, and proposes greater than 5,000 square feet of new and replaced pollution generating hard surface area. Enhanced treatment, and phosphorus removal is required to be provided in this project's stormwater design. Enhanced treatment, and phosphorus removal will be provided by a Bio clean Environmental MWS-Linear Modular Wetland system that will treat stormwater runoff off-line and upstream of the proposed detention facility. Additionally oil control will be provided by an off-line oil/water separator located upstream of the proposed treatment facility.

ROW PGHS


All runoff from new and replaced pollution generating hard surfaces within the right-of-way cannot be feasibly isolated and treated from runoff of the adjacent road surfaces. This project will provide treatment for an area within the right-of-way greater than or equal to the proposed new and replaced pollution generating hard surfaces that will bypass the on-site facility. Treatment within the right-of-way will be provided by a Contech Stormfilter Catch basin.

Figure 5.9 Contech WQ Basin Map





CONTECH WQ BASIN MAP
FOR
BROWN BEAR CAR WASH
SE 1/4 OF NE 1/4 OF SEC. 28, TWN. 24 N, RGE. 6 E, W.M.
CITY OF ISSAQUAH, KING COUNTY, WASHINGTON



PER CITY REVIEW COMMENTS RECEIVED 02/19/2020			
LAND USE SUBMITTAL			
No.	Date	By	Appr.
2	4/3/2020	ADW / AEM	CRJ
1	11/15/19	ADW / AEM	CRJ


Title:
CONTECH WQ BASIN MAP
BROWN BEAR CAR WASH
55 NW GILMAN BLVD.
ISSAQUAH, WA

For:
CAR WASH ENTERPRISES, INC.
3977 LEARY WAY NW
SEATTLE, WASHINGTON 98107

4/3/2020

Designed ADW		Scale:	
Drawn	ADW	Horizontal	1" = 10'
Checked	AEM	Vertical	NA
Approved	CRJ		
Date	11/15/19		

Barghausen
Consulting Engineers, Inc.
18215 72nd Avenue South
Kent, WA 98032
425.251.6222 barghausen.com



Job Number
20693
Sheet
1 of 1



Know what's below.
Call before you dig.
Dial 811

5.7 Conveyance System Analysis and Design

All proposed conveyance systems are anticipated to provide adequate capacity for on-site runoff flows. Conveyance system calculations may be provided upon a subsequent submittal at the request of the City of Issaquah.

Tab 6.0

6.0 CONSTRUCTION STORMWATER POLLUTION PREVENTION PLAN

THE FOLLOWING IS A LIST OF THE TWELVE SWPPP ELEMENTS AND HOW THEY HAVE BEEN ADDRESSED FOR THIS PROJECT:

Element No. 1 - Preserve Vegetation / Mark Clearing Limits: Clearing Limits will be delineated on the engineering plans and will be flagged in the field.

Element No. 2 - Establish Construction Access: A stabilized gravel construction entrance will be shown on the engineering plans. Construction access will be taken from the Alley located along the project's east boundary.

Element No. 3 - Control Flow Rates: A temporary sediment ponds will be shown on the engineering plans. Once the permanent detention facilities are constructed the temporary sediment ponds can be removed. The permanent facilities can be used throughout the remainder of construction.

Element No. 4 - Install Sediment Controls: Silt fence will be shown on the engineering plans for perimeter protection. In addition, temporary ditches to divert runoff to the sediment pond will be shown on the engineering plans.

Element No. 5 - Stabilize Soils: Cover measures will be addressed in the TESC notes on the engineering plans.

Element No. 6 - Protect Slopes: There are no significant slopes onsite, existing or proposed that require additional measures beyond the soil stabilization measures to be shown on the engineering plans.

Element No. 7 - Protect Permanent Drain Inlets: A detail for catch basin inserts will be shown on the final engineering plans along with a note specifying that they be installed once the permanent storm system is completed. A note will also be included that the contractor shall keep public roadways clear of dirt and debris.

Element No. 8 - Stabilize Channels and Outlets: Notes regarding outfall protection will be shown on the engineering plans. Temporary ditches shall be armored with rip rap for slopes greater than 5 percent.

Element No. 9 - Control Pollutants: A note will be added to the engineering plans that the contractor shall dispose of all pollutants and waste materials in a safe and timely manner.

Element No. 10 - Control Dewatering: Notes will be added to the engineering plans stating that water in underground utility trenches or low spots are to be routed to the temporary sediment pond via temporary ditches or perforated rock drains.

Element No. 11 - Maintain Best Management Practices Once the engineering plans are completed the contractor shall maintain all erosion control measures in accordance with City of Issaquah and manufactures recommendations. In addition, the contractor shall maintain a stockpile of erosion control materials onsite.

Element No. 12 - Manage the Project: Once the engineering plans are completed, the clearing, grading, and seasonal work shall be performed in accordance with the City of Issaquah. The contractor shall inspect, maintain, and repair all BMPs as needed to assure continued performance of their intended function. In addition to the engineering plans the contractor will be required to follow and maintain the Construction SWPPP which has been prepared according to Department of

Ecology NPDES Requirements. The completed SWPPP and TESC Plans will be provided during Final Engineering Review.

Element No. 13 – Protect Low Impact Development BMPs: Areas that apply BMP T5.13: Post Construction Soil Quality and Depth must be protected from vehicular compaction and excessive foot traffic.

Tab 7.0

7.0 SPECIAL REPORTS AND STUDIES

- 1) *Geotechnical Engineering Report
Brown Bear Car Wash
55 Northwest Gilman Boulevard
Issaquah, Washington*

Prepared by: Aspect Consulting
 710 2nd Avenue, Suite 500
 Seattle, WA 98104
 Tel: (206) 780-7727

GEOTECHNICAL ENGINEERING REPORT

BROWN BEAR CAR WASH

55 Northwest Gilman Boulevard
Issaquah, Washington

Prepared for: Car Wash Enterprises, Inc.

Project No. 080109 • November 7, 2019 DRAFT



e a r t h + w a t e r



GEOTECHNICAL ENGINEERING REPORT BROWN BEAR CAR WASH

55 Northwest Gilman Boulevard
Issaquah, Washington

Prepared for: Car Wash Enterprises, Inc.

Project No. 080109 • November 7, 2019 • DRAFT

Aspect Consulting, LLC



Rory Kilkenny, PE
Geotechnical Engineer
rkilkenny@aspectconsulting.com

Henry H. Haselton, PE
Principal Geotechnical Engineer
hhaselton@aspectconsulting.com

V:\080109 Car Wash Enterprises\Deliverables\001-12 Gilman Blvd\Geotechnical Study\DRAFT\Issaquah Brown Bear_DRAFT_20191107.doc

Contents

1	Introduction	1
1.1	Project Description	1
2	Site Conditions	2
2.1	Surface	2
2.2	Subsurface Conditions	2
2.2.1	General Geology	2
2.2.2	Stratigraphy	2
2.2.3	Groundwater.....	3
2.2.4	Critical/Geologically Hazardous Areas	3
3	Seismic Hazard Evaluation.....	4
3.1	Seismic Design Parameters	4
3.2	Liquefaction Susceptibility	5
3.3	Surficial Ground Rupture	5
4	Geotechnical Engineering Conclusions and Recommendations	6
4.1	Shallow Foundations on Fill.....	6
4.1.1	Allowable Bearing Pressure.....	6
4.1.2	Settlement	6
4.1.3	Lateral Resistance	6
4.2	Slabs-on-Grade	6
4.3	Construction Dewatering	7
4.4	Pavement Design and Construction Considerations.....	7
4.5	Stormwater Infiltration.....	7
5	Earthwork Considerations and Recommendations	8
5.1	Temporary Excavation Slopes.....	8
5.2	Subgrade Preparation	8
5.2.1	Shallow Foundations	8
5.2.2	Slabs-on-Grade and Pavements.....	9
5.2.3	Pavement	9
5.3	Structural Fill	9
5.4	Utility Bedding and Backfill	10
5.5	Temporary Erosion and Sedimentation Control	10
5.6	Wet Weather Construction.....	11

6	Additional Design and Construction Monitoring	12
7	References	13
8	Limitations.....	14

List of Tables

1	Seismic Design Parameters	5
----------	--	----------

List of Figures

1	Site Location Map
2	Geotechnical Explorations Plan

List of Appendices

A	Subsurface Explorations
B	Report Limitations and Guidelines for Use

1 Introduction

This report presents the results of a geotechnical engineering study completed by Aspect Consulting, LLC (Aspect) on behalf of Car Wash Enterprises, Inc. (CWE) to fulfill the City of Issaquah requirement for a Soils Report for the Brown Bear Car Wash redevelopment (Project) located at 55 NW Gilman Blvd in Issaquah, Washington (Site; Figure 1). This report is intended to be used as an attachment for the City of Issaquah Land Use permit; it is for planning purposes only and not to be used as a stand-alone document.

This report summarizes explorations and geotechnical data collected to date, and presents our geotechnical engineering conclusions and recommendations based on the geotechnical data and current building concepts. The information and recommendations presented in this report are intended to assist the design team in the selection of foundation alternatives, construction methods, and to inform construction cost estimates for the Project.

1.1 Project Description

The Site has a history of use as a gasoline service station and car care facility. Environmental impacts are present in the Site soil and groundwater as a result of the historical operations. CWE has been conducting an environmental remediation in conjunction with plans to redevelop the Site as a car wash facility. Previous cleanup efforts included excavation of impacts to depths of 13 feet below ground surface and backfilling with clean fill, while future cleanup efforts will likely include the installation of an air sparging/soil vapor extraction (AS/SVE) system to treat deeper impacts. The current use of the site is a level gravel pad.

The proposed redevelopment of the Site includes the design and construction of a new Brown Bear Car Wash. The proposed 3,500 square foot car wash building is expected to consist of a single-story structure supported by shallow spread or strip footings bearing directly on the fill placed during the previous cleanup efforts. Foundation loads are expected to be typical of a building of this type and size. Small amounts of subsurface grading are expected to be required to install below-grade utilities and to manage Site drainage. Aspect's current understanding of the proposed development can be found on Figure 2.

2 Site Conditions

2.1 Surface

Current Site surface conditions consist a generally flat gravel pad, which has been backfilled after a recent remedial excavation. The western edge of the Site is bound by 1st Avenue NW. The eastern and northern edge of the Site is bound by an alley. The southern edge of the Site is bound by the Valvoline Instant Oil Change property.

2.2 Subsurface Conditions

The subsurface conditions at the Site were inferred from our review of geologic maps and explorations advanced at the Site by Aspect. The explorations by Aspect consisted of two hollow-stem auger borings. The location of these borings is shown on Figure 2. A detailed description of the exploration methods used, and our exploration logs are provided in Appendix A.

2.2.1 *General Geology*

The geologic map of Issaquah maps the Site as being underlain by Holocene Fan deposits (Booth, 2006). These deposits generally consist of boulders, cobbles, sand, and diamict deposited in a lobate form where streams emerge from confining valleys, and the reduced gradients cause some of their sediment loads to be deposited. These units generally grade with Holocene alluvium deposits.

2.2.2 *Stratigraphy*

Based on the completed subsurface explorations, we grouped the Site soils into two units: fill, and alluvium. Based on our understanding of the Site and our explorations, fill was placed to backfill the Site from a recent environmental remediation excavation a raise grades back to ground surface, as needed, throughout the Site.

The composition and distribution of these units are summarized below. For more detailed information regarding the composition and distribution of these units, please refer to the exploration logs provided in Appendix A.

Fill

Up to about 13 feet of fill was observed in our explorations ASB-01 and ASB-02. The fill typically consisted of medium dense to very dense, moist, brown and gray, silty gravel with sand (GM).

Alluvium

Alluvium was observed in both borings, AB-01 and AB-02 from depths of about 13 feet to the termination depths of the borings. The outwash generally consisted of medium dense to very dense, wet, brown and gray, gravel and sand with varying amount of silt

(GM and SM). A two-foot-thick layer of medium stiff silt with sand was also encountered from 13 to 15 feet below ground surface in ASB-01,

2.2.3 *Groundwater*

Groundwater levels were inferred from sample moisture at the time of drilling to be approximately 12 to 15 feet bgs. Groundwater levels at the Site are expected to fluctuate seasonally with changes in precipitation, Site usage, and other factors.

2.2.4 *Critical/Geologically Hazardous Areas*

Typical critical and geologically hazardous areas present in the Puget Sound area include landslide, erosion, liquefaction, wetland, and fault ground rupture critical/hazard areas. Based on the Site location, topography, surface conditions, and subsurface conditions, we conclude that of these critical/geologically hazardous areas, only liquefaction is relevant to the Site. The Washington Geologic Information Portal (DNR, 2019) indicates that of these hazard areas, the Site has a moderate to high susceptibility to liquification. The liquefaction susceptibility is further described in Section 3.2.

The Site is located in a seismically active region and subject to strong ground shaking during earthquakes. Accordingly, new structures should be designed to account for ground shaking in accordance with the current applicable building codes.

3 Seismic Hazard Evaluation

The Site is located within a region of active tectonic forces associated with the interaction of the offshore Juan de Fuca Plate, the Pacific Plate, and the onshore North American Plate. Seismic hazards include strong ground shaking from earthquakes associated with the Seattle Fault Zone (SFZ), the Cascadia Subduction Zone (CSZ), and deep intraslab earthquakes.

The SFZ is a zone of east-west thrust faults. The U.S. Geological Survey (USGS) estimates that the SFZ can produce earthquakes of magnitude 7.0 or greater. The last large earthquake on this fault system occurred about 1,100 years ago and resulted in up to 27 feet of uplift in parts of West Seattle.

The CSZ lies along the boundary of the converging oceanic plates (Juan de Fuca and Pacific Plates) and continental plate (North American Plate). CSZ earthquakes occur due to rupture between the subducting oceanic plate and the overlying continental plates. The CSZ can produce earthquakes up to magnitude 9.3, and the recurrence interval is thought to be on the order of about 500 years. The most recent subduction zone earthquake was estimated to occur about 300 years ago.

Deep intraslab earthquakes, which occur from tensional rupture of the sinking oceanic plate, are also associated with the CSZ. An example of this type of seismicity is the 2001 Nisqually earthquake. Deep intraslab earthquakes typically are magnitude 7.5 or less and occur approximately every 10 to 30 years.

3.1 Seismic Design Parameters

Seismic design for the Project will be for a “Maximum Considered Earthquake” (MCE) with an earthquake ground motion that has 2 percent probability of exceedance in 50 years, or a return period of approximately 2,500 years. The effects of Site-specific subsurface conditions on the earthquake ground motion at the ground surface are determined based on the “Site Class.” The Site Class can be correlated to the average standard penetration resistance (N-value) or average shear wave velocity in the upper 100 feet of the soil profile. Based on the subsurface explorations completed at the Site, the soil profile below each building would classify as Site Class D (Stiff Soil Profile).

We understand the buildings will be permitted after the adoption of the 2018 International Building Code (IBC) and the American Society of Civil Engineers (ASCE) 7-16, *Minimum Design Loads for Buildings and Other Structures* (ASCE, 2017). The seismic design parameters, in accordance with the 2018 IBC and ASCE 7-16, and adjusted for Site Class D, are provided in Table 1.

Table 1. Seismic Design Parameters

Ground Motion Parameter	Recommended Value
Site Class	D– “Stiff Soil”
Short Period Spectral Acceleration, S_s (g)	1.311
1-Second Period Spectral Acceleration, S_1 (g)	0.453
Site Coefficient (F_a)	1.0
Site Coefficient (F_v)	1.847
Design Short Period Spectral Acceleration, S_{DS} (g)	0.874
Design 1-Second Period Spectral Acceleration, S_{D1} (g)	0.558
Site-Adjusted Peak Ground Acceleration (g)	0.616

Note: Parameters based on the latitude and longitude of the Site: 47.537973°N, 122.037268°W

3.2 Liquefaction Susceptibility

Liquefaction occurs when loose, saturated, and relatively cohesionless soil deposits temporarily lose strength and stiffness as a result of earthquake shaking. Potential effects of soil liquefaction include temporary loss of shallow-foundation bearing capacity, loss of deep-foundation axial and lateral capacity, vertical ground settlement, creekbank slope failure, and lateral ground movement towards creek banks or shoreline areas—any of which could result in structural damage. Primary factors controlling the triggering of liquefaction include intensity and duration of strong ground motion, characteristics of subsurface soils, *in situ* stress conditions, and the depth to groundwater.

Our explorations reveal that below the groundwater table, soils have sufficient relative density or plasticity/cohesiveness to render them nonsusceptible to liquefaction. Therefore, we conclude that liquefaction is not a design consideration at the Site.

3.3 Surficial Ground Rupture

Due to the suspected long recurrence interval, and the distance of the Site from the nearest known strand of the SFZ, and the great distance of the site from the CSZ, the potential for surficial ground rupture at the Site is considered low during the expected life of the structure.

4 Geotechnical Engineering Conclusions and Recommendations

4.1 Shallow Foundations on Fill

4.1.1 *Allowable Bearing Pressure*

In our opinion, shallow spread footings are feasible for the new building. Shallow foundations bearing directly on fill soils may be designed for an allowable bearing pressure of 3 kips per square foot (ksf). This allowable bearing pressure assumes the foundations are embedded a minimum of 24 inches below the ground surface and a minimum square footing dimension of 3 feet or a strip footing width of 2.5 feet. The allowable bearing pressure may be increased by one-third for short-duration loading, such as wind and seismic loading.

4.1.2 *Settlement*

We estimate footings bearing on the fill and designed in accordance with our recommendations will experience average total settlements of 1 inch or less. Differential settlements between adjacent column footings can be assumed to be about one-half of the total settlement. Differential settlement along continuous strip footings can be assumed to be approximately 0.5 inches per 25 feet of footing length. Total and differential settlement will occur rapidly as building loads are applied.

4.1.3 *Lateral Resistance*

To resist lateral loading, we recommend using an allowable passive equivalent fluid density of 300 pounds per cubic foot and an allowable base friction coefficient of 0.33 for foundations embedded in the fill. These allowable values include a factor of safety of 1.5.

4.2 Slabs-on-Grade

Concrete slabs-on-grade for the car wash building should be designed in accordance with the American Concrete Institute (ACI) Committee 360 Guide to Design of Slabs-on-Ground (ACI, 2010). We recommend the slab be underlain with 6 inches of free-draining, crushed rock or well-graded sand and gravel to provide a uniform support. The crushed rock material should have a maximum particle size of 3/4 inch, with no more than 80 percent passing the No. 4 sieve and less than 5 percent fines (material passing the U.S. Standard No. 200 sieve).

For slabs that are designed as beam-on-elastic foundation, a modulus of subgrade reaction of 200 pounds per cubic inch (pci) may be assumed for design.

4.3 Construction Dewatering

We do not expect the excavations for the shallow foundations to encounter groundwater. If small amounts of groundwater are encountered during construction, we expect it can be managed using sumps and pumps at the discretion of the contractor.

4.4 Pavement Design and Construction Considerations

We anticipate new access driveway areas and passenger vehicle parking areas will be paved with flexible hot mix asphalt (HMA). In asphalt driveway or parking areas where heavy trucks are anticipated to operate, we recommended the pavement section consist of 3 inches of HMA over 6 inches of crushed surfacing base and top course.

We recommend Crushed Surfacing Base Course (CSBC) for the pavement base course, and Crushed Surfacing Top Course (CSTC) may be used over the CSBC for the upper 2 to 3 inches of the base course section. CSBC and CSTC, as specified in Section 9-03.9(3) of the *Standard Specifications* (WSDOT, 2019), should be used as base course for pavements.

4.5 Stormwater Infiltration

The City of Issaquah utilizes the Washington State Department of Ecology Water Quality Program *Stormwater Management Manual for Western Washington* (SWMMWW; Ecology, 2014). The SWMMWW states that utilizing infiltrating BMPs is infeasible for properties within 100 feet of an area known to have deep soil contamination. Due to the presence of environmentally impacted soil and groundwater beneath the Site, we consider shallow stormwater infiltration to be inadvisable. We recommend stormwater management be accomplished utilizing storm drainpipes that discharge into an appropriate system which will not infiltrate into the groundwater.

5 Earthwork Considerations and Recommendations

Excavation for the Project will occur mostly in dense sand and gravel fill. We anticipate excavation can take place with standard excavation equipment, such as tracked excavators.

5.1 Temporary Excavation Slopes

Temporary excavation slopes will be required for installation of spread footings and utilities. Temporary excavation and slopes should not exceed the limits specified in the local, state, and federal regulations. The stability of temporary excavations and slopes shall be the responsibility of the contractor. The fill deposits are classified as Type C soil in accordance with the Washington Administrative Code (WAC) 296-155 Part N (WAC, 2016). Temporary excavation slopes in Type C soils are anticipated to stand as steep as 1.5H:1V (Horizontal:Vertical). If unexpected seepage is encountered, the temporary excavation slopes may be required to be flattened to remain stable.

We also recommend the following:

- Surface water should be diverted away from slopes.
- Protect slopes using plastic sheet, flash coating, or tarps to control erosion and stability, as necessary.
- Limit the duration that excavations or slopes are open to the shortest time possible.
- Traffic, equipment, and material stockpiles should not be allowed near the top of excavations or slopes.
- The conditions of the excavations and slopes should be periodically observed by a competent person, who is a representative of the contractor, to evaluate safety and stability.

5.2 Subgrade Preparation

5.2.1 *Shallow Foundations*

Foundation subgrades should be firm and unyielding and clear of all construction debris, loose or disturbed soil, and standing water prior to foundation construction. Soft or disturbed foundation subgrade areas, such as organic material, should be removed and replaced with structural fill. If organic material is encountered, it should be overexcavated until the competent fill is exposed and replaced with structural fill to reach the desired grade. Foundation preparation should be observed by Aspect prior to placing steel and pouring concrete to verify they have been prepared in conformance with our recommendations.

5.2.2 **Slabs-on-Grade and Pavements**

Slab-on-grade subgrade preparation should be observed and evaluated by a representative of Aspect prior to placement of the concrete or pavement section. All subgrade should be firm and unyielding under the proof-rolling load of heavy rubber-tired equipment where accessible and should be clear of any loose or disturbed soil or standing water. Disturbed or soft subgrade areas identified during evaluation should be removed and replaced with structural fill.

5.2.3 **Pavement**

The near-surface fill will provide suitable support for new pavement sections provided that any zones of concentrated organics and deleterious debris are removed from the pavement subgrade. All pavement subgrades should be carefully prepared. Prior to placing base course and pavement, all standard pavement subgrades should be proof-rolled with a fully loaded 10-cubic-yard dump truck or equivalent. An Aspect geotechnical engineer or engineering geologist should observe and evaluate the proof rolling operation. Any soft areas detected by the proof-rolling or other methods should be compacted in place or overexcavated to firm ground and backfilled with compacted structural fill to the design subgrade elevation. To provide for quality construction practices and materials, we recommend all pavement work and mix-design considerations conform to WSDOT standards.

The recommended pavement section is not intended to support extensive construction traffic, such as dump trucks and concrete Redi-mix trucks. Pavements subject to heavy construction traffic may be damaged and require repair.

Drainage is an essential aspect of pavement performance. We recommend providing all paved areas with positive drainage to remove surface water and water within the base course. This will be particularly important in cut sections or at low points within the paved areas, such as at catch basins.

5.3 **Structural Fill**

Soils placed beneath or around foundations, walls, utilities, slabs-on-grade, or below pavements should be considered structural fill. For these fill areas, we provide the following recommendations:

- Site-derived fill soils are suitable for reuse as structural fill but may be difficult to compact during wet weather. Additional fill can be imported per the recommendations below. Organic material or any soils with deleterious matter cannot be reused as structural fill.
- Structural fill to be used below foundations (for removal and replacement scenarios) can consist of appropriate on-Site material or crushed rock meeting the requirements for WSDOT Standard Specification Crushed Surfacing 9-03.9(3) (WSDOT, 2018).
- Structural fill should only be placed on a relatively firm and unyielding subgrade. The exposed subgrade soils should be compacted (in place) to a dense and unyielding condition prior to placement of structural fill.

- Structural fill should be compacted to a relatively firm and unyielding condition to a minimum density of 95 percent of the maximum dry density as determined by ASTM International (ASTM) D1557 (ASTM, 2018).
- Structural fill should be placed in lifts with a loose thickness no greater than 12 inches when using relatively large compaction equipment, such as a vibrating plate attached to an excavator (hoe pack) or drum roller. If small, hand-operated compaction equipment is used to compact structural fill, lifts should not exceed 6 inches in loose thickness.
- Moisture content of the structural fill should be controlled to within 2 to 3 percent of the optimum moisture. Optimum moisture is the moisture content corresponding to the maximum modified proctor dry density.
- Fill placed in softscape, general grading, landscape, or common areas that are not beneath or around structures, utilities, slabs-on-grade, or below paved areas that can accommodate some settlement should be compacted to a relatively firm and unyielding condition.

5.4 Utility Bedding and Backfill

General recommendations for bedding of utilities and backfill of utility trenches include:

- Materials to be used for utility bedding should consist of appropriate onsite material, meet the requirements WSDOT Standard Specification 9-03.9(3), or be as specified in the Standard Specification section applicable to the type of pipe being installed.
- Prior to installation of the pipe, the bedding material should be shaped to fit the lower portion of the pipe exterior with reasonable closeness to provide continuous support along the pipe.
- Bedding placed around the pipe should be placed in layers and tamped around the pipe to obtain complete contact. Pipe bedding material should be used as trench backfill to at least 6 inches above the crown of the pipe, for the full width of the trench. In areas where a trench box is used, the bedding material should be placed before the trench box is advanced.
- Trench backfill should meet the requirements for Structural Fill as described in Section 5.3 of this report. During placement of the initial lifts, the trench backfill material should not be bulldozed into the trench or dropped directly on the pipe. Furthermore, heavy vibratory equipment should not be permitted to operate over the pipe until at least 2 feet of backfill has been placed.

5.5 Temporary Erosion and Sedimentation Control

Temporary erosion-control measures should be implemented to prevent the migration of soil, dust, and turbid water off-Site or into stormwater systems. Such measures should include silt fences and straw wattles at the Site boundary, silt socks in nearby catch basins, wetting exposed soil during dry periods, and quarry spalls and wheel wash stations at truck and equipment exits.

5.6 Wet Weather Construction

Earthwork is typically most economical when performed under dry weather conditions. If earthwork is to be performed or fill is to be placed in wet weather or under wet conditions, we provide the following recommendations:

- Earthwork should be performed in small areas to minimize exposure to wet weather. The size and type of construction equipment used may have to be limited to prevent soil disturbance.
- Excavations for foundations, floor slabs, and pavements should be covered or protected (with concrete or WSDOT Standard Specification 9-03.9(3)) following approval of the subgrade by Aspect and should not be left open and exposed.
- Material used as structural fill should consist of clean, granular soil containing less than 7 percent fines.
- The ground surface within the construction area should be sealed by a smooth drum vibratory roller (or equivalent) and under no circumstances should be left uncompacted and exposed to moisture. Soils which become too wet for compaction should be removed and replaced with clean granular materials.
- Excavation and placement of fill should be observed by Aspect to verify that all unsuitable materials are removed, and suitable compaction is achieved.
- Local best management practices (BMPs) for erosion protection should be strictly followed.

6 Additional Design and Construction Monitoring

At the time of this report, concept Site plans, Site grading, structural plans, and construction methods have not been developed or finalized, and the recommendations presented herein are based on preliminary project information. If project developments result in changes to the assumptions made herein, we should be contacted to determine if our recommendations should be revised. We recommend that we have an opportunity to review and provide input on Site development plans as they are advanced to ensure that the recommendations of this report are appropriately incorporated into the Site design.

We are available to provide geotechnical engineering and monitoring services during construction. The integrity of the foundation depends on proper site preparation and construction procedures. In addition, engineering decisions may have to be made in the field in the event that variations in subsurface conditions become apparent.

7 References

- American Concrete Institute (ACI) Committee 360, 2010, Guide to Design of Slabs-on-Ground.
- American Society of Civil Engineers (ASCE), 2017, 7-16, Minimum Design Loads for Buildings and Other Structures.
- ASTM International (ASTM), 2018, 2018 Annual Book of ASTM Standards, West Conshohocken, Pennsylvania.
- Goldsmith Land Development Services (Goldsmith), 2017, ATLA/NSPS Land Title Survey for Lake Union Partners, Sheet 1 of 2 and 2 of 2, August 24, 2017.
- Washington State Department of Ecology Water Quality Program (Ecology), 2014, 2014 Stormwater Management Manual for Western Washington.
- Washington State Department of Natural Resources Division of Geology and Earth Resources (DNR), 2019, Washington Interactive Geologic Map, 2019, online at: <https://fortress.wa.gov/ndr/protectiongis/geology/?Theme=wigm>.
- Washington State Department of Transportation (WSDOT), 2019, Standard Specifications for Road, Bridge and Municipal Construction, Document M 41-10.
- Washington State Legislature, 2016, Washington Administrative Code (WAC), May 20, 2016.

8 Limitations

Work for this project was performed for Car Wash Enterprises, Inc. (Client), and this report was prepared consistent with recognized standards of professionals in the same locality and involving similar conditions, at the time the work was performed. No other warranty, expressed or implied, is made by Aspect Consulting, LLC (Aspect).

Recommendations presented herein are based on our interpretation of site conditions, geotechnical engineering calculations, and judgment in accordance with our mutually agreed-upon scope of work. Our recommendations are unique and specific to the project, site, and Client. Application of this report for any purpose other than the project should be done only after consultation with Aspect.

Variations may exist between the soil and groundwater conditions reported and those actually underlying the site. The nature and extent of such soil variations may change over time and may not be evident before construction begins. If any soil conditions are encountered at the site that are different from those described in this report, Aspect should be notified immediately to review the applicability of our recommendations.

It is the Client's responsibility to see that all parties to this project, including the designer, contractor, subcontractors, and agents, are made aware of this report in its entirety. At the time of this report, design plans and construction methods have not been finalized, and the recommendations presented herein are based on preliminary project information. If project developments result in changes from the preliminary project information, Aspect should be contacted to determine if our recommendations contained in this report should be revised and/or expanded upon.


The scope of work does not include services related to construction safety precautions. Site safety is typically the responsibility of the contractor, and our recommendations are not intended to direct the contractor's site safety methods, techniques, sequences, or procedures. The scope of our work also does not include the assessment of environmental characteristics, particularly those involving potentially hazardous substances in soil or groundwater.

All reports prepared by Aspect for the Client apply only to the services described in the Agreement(s) with the Client. Any use or reuse by any party other than the Client is at the sole risk of that party, and without liability to Aspect. Aspect's original files/reports shall govern in the event of any dispute regarding the content of electronic documents furnished to others.


Please refer to Appendix B titled "Report Limitations and Guidelines for Use" for additional information governing the use of this report.


We appreciate the opportunity to perform these services. If you have any questions, please call Rory Kilkenny PE, Geotechnical Engineer, at 541.256.0037.

FIGURES



Site Location Map
Geotechnical Engineering Report
Car Wash Enterprises
55 NW Gilman Boulevard
Issaquah, Washington

	NOV-2019	BY: RPK / WEG	FIGURE NO. 1
	PROJECT NO. 080190	REVISED BY: ---	



Notes:

1. Current site conditions consist of gravel pad; proposed site conditions shown.
2. Vertical datum NAVD 88, based on GPS measurements using the Washington State Reference Network.

DRAFT


Legend



Boring Location



2019 Remedial
Excavation Boundary



0 30 60 Feet

Source: Base map provided by Barghausen Consulting Engineers, Inc., dated November 5, 2019.

Geotechnical Exploration Plan

Car Wash Enterprises
55 NW Gilman Boulevard
Issaquah, Washington



Nov-2019

PROJECT NO.
080109

BY:
RK/CMV

REVISED BY:
-

FIGURE NO.

2

APPENDIX A

Subsurface Explorations

A.1 Field Exploration Program






















A.1.1 Hollow-Stem Auger Borings

On October 18, 2019, Aspect Consulting, LLC (Aspect) completed two machine-drilled borings (designated ASB-01 and ASB-02) at the Site. The machine-drilled borings were advanced with hollow-stem auger drilling methods using a CME 75 truck-mounted drill rig operated by Cascade Drilling under subcontract to Aspect.

In the machine-drilled borings, disturbed soil samples were obtained at 2.5- and 5-foot intervals by driving a 2-inch split-barrel sampler (SPT sampler) 18 inches into the soil with a 140-pound hammer free-falling a distance of 30 inches. The number of blows required to drive the sampler 18 inches is recorded in three 6-inch intervals. The number of blows required to drive the sampler the last two intervals is known as the blow count. The blow count provides a measure of relative density or consistency of granular and cohesive soils, respectively.

An Aspect geotechnical engineer was present throughout the exploration program to observe the drilling procedures, assist in sampling, and to prepare descriptive logs of the explorations. Soils were identified in general accordance with ASTM International (ASTM) D2488, *Standard Practice for Description and Identification of Soils (Visual-Manual Procedure)* (ASTM, 2018). The summary exploration logs represent our interpretation of the contents of the field logs. The stratigraphic contacts shown on the individual summary logs represent the approximate boundaries between soil types; actual transitions may be more gradual. The subsurface conditions depicted are only for the specific date and locations reported; therefore, are not necessarily representative of other locations and times.

Upon completion, the machine-drilled borings were backfilled with 3/8-inch bentonite chips in accordance with requirements of the Washington State Department of Ecology.

Coarse-Grained Soils - More than 50% ¹ Retained on No. 200 Sieve			
	Sands - 50% ¹ or More of Coarse Fraction Passes No. 4 Sieve	Gravels - More than 50% ¹ of Coarse Fraction Retained on No. 4 Sieve	
		≤5% Fines	≥15% Fines
Fine-Grained Soils - 50% ¹ or More Passes No. 200 Sieve	Silts and Clays Liquid Limit Less than 50%		
			
			
			
			
	Silts and Clays Liquid Limit 50% or More		
			
			
			
			
Highly Organic Soils			
			
			
			

"WITH SILT" or "WITH CLAY" means 5 to 15% silt and clay, denoted by a "-" in the group name; e.g., SP-SM • "SILTY" or "CLAYEY" means >15% silt and clay • "WITH SAND" or "WITH GRAVEL" means 15 to 30% sand and gravel. • "SANDY" or "GRAVELLY" means >30% sand and gravel. • "Well-graded" means approximately equal amounts of fine to coarse grain sizes • "Poorly graded" means unequal amounts of grain sizes • Group names separated by "/" means soil contains layers of the two soil types; e.g., SM/ML.

Soils were described and identified in the field in general accordance with the methods described in ASTM D2488. Where indicated in the log, soils were classified using ASTM D2487 or other laboratory tests as appropriate. Refer to the report accompanying these exploration logs for details.

1. Estimated or measured percentage by dry weight
2. (SPT) Standard Penetration Test (ASTM D1586)
3. Determined by SPT, DCPT (ASTM STP399) or other field methods. See report text for details.

GEOTECHNICAL LAB TESTS	
MC	= Natural Moisture Content
GS	= Grain Size Distribution
FC	= Fines Content (% < 0.075 mm)
GH	= Hydrometer Test
AL	= Atterberg Limits
C	= Consolidation Test
Str	= Strength Test
OC	= Organic Content (% Loss by Ignition)
Comp	= Proctor Test
K	= Hydraulic Conductivity Test
SG	= Specific Gravity Test

CHEMICAL LAB TESTS	
Organic Chemicals	
BTEX	= Benzene, Toluene, Ethylbenzene, Xylenes
TPH-Dx	= Diesel and Oil-Range Petroleum Hydrocarbons
TPH-G	= Gasoline-Range Petroleum Hydrocarbons
VOCs	= Volatile Organic Compounds
SVOCs	= Semi-Volatile Organic Compounds
PAHs	= Polycyclic Aromatic Hydrocarbon Compounds
PCBs	= Polychlorinated Biphenyls

Metals	
RCRA8	= As, Ba, Cd, Cr, Pb, Hg, Se, Ag, (d = dissolved, t = total)
MTCA5	= As, Cd, Cr, Hg, Pb (d = dissolved, t = total)
PP-13	= Ag, As, Be, Cd, Cr, Cu, Hg, Ni, Pb, Sb, Se, Tl, Zn (d=dissolved, t=total)

FIELD TESTS	
PID	= Photoionization Detector
Sheen	= Oil Sheen Test
SPT ²	= Standard Penetration Test
NSPT	= Non-Standard Penetration Test
DCPT	= Dynamic Cone Penetration Test

Descriptive Term	Size Range and Sieve Number	COMPONENT DEFINITIONS
Boulders	= Larger than 12 inches	
Cobbles	= 3 inches to 12 inches	
Coarse Gravel	= 3 inches to 3/4 inches	
Fine Gravel	= 3/4 inches to No. 4 (4.75 mm)	
Coarse Sand	= No. 4 (4.75 mm) to No. 10 (2.00 mm)	
Medium Sand	= No. 10 (2.00 mm) to No. 40 (0.425 mm)	
Fine Sand	= No. 40 (0.425 mm) to No. 200 (0.075 mm)	
Silt and Clay	= Smaller than No. 200 (0.075 mm)	

% by Weight	Modifier	% by Weight	Modifier	ESTIMATED ¹ PERCENTAGE
<1	= Subtrace	15 to 25	= Little	
1 to <5	= Trace	30 to 45	= Some	
5 to 10	= Few	>50	= Mostly	

MOISTURE CONTENT	
Dry	= Absence of moisture, dusty, dry to the touch
Slightly Moist	= Perceptible moisture
Moist	= Damp but no visible water
Very Moist	= Water visible but not free draining
Wet	= Visible free water, usually from below water table

RELATIVE DENSITY	
Non-Cohesive or Coarse-Grained Soils	
Density³	SPT² Blows/Foot
Very Loose	= 0 to 4
Loose	= 5 to 10
Medium Dense	= 11 to 30
Dense	= 31 to 50
Very Dense	= > 50

CONSISTENCY	
Cohesive or Fine-Grained Soils	
Consistency³	SPT² Blows/Foot
Very Soft	= 0 to 1
Soft	= 2 to 4
Medium Stiff	= 5 to 8
Stiff	= 9 to 15
Very Stiff	= 16 to 30
Hard	= > 30

GEOLOGIC CONTACTS	
Observed and Distinct	Observed and Gradual
Inferred	

Aspect CONSULTING	Exploration Log Key
-------------------	---------------------



Brown Bear - Issaquah - 080109

Project Address & Site Specific Location
55 NW Gilman Blvd Issaquah, WA 98027, W of Chevron Station, SE of ASB-02

Geotechnical Exploration Log

Coordinates (Lat, Lon WGS84)

47.53796, -122.03722 (est)

Exploration Number

ASB-01

Contractor

Cascade

Operator

James

Equipment

CME 75 truck rig

Exploration Method(s)

Hollow stem auger

Sampling Method

Autohammer; 140 lb hammer; 30" drop

Work Start/Completion Dates

10/18/2019

Ground Surface (GS) Elev. (NAVD88)


77' (est)

Top of Casing Elev. (NAVD88)

NA

Depth to Water (Below GS)

15' (ATD)



Legend

□ No Soil Sample Recovery

■ Split Barrel 2" X 1.375" (SPT)

Plastic Limit — Liquid Limit

▽ Water Level ATD

Water Level

See Exploration Log Key for explanation of symbols

Logged by: IVT
Approved by: RPK

Exploration Log
ASB-01

Sheet 1 of 2



Brown Bear - Issaquah - 080109

Project Address & Site Specific Location
55 NW Gilman Blvd Issaquah, WA 98027, W of Chevron Station, NW of ASB-01

Geotechnical Exploration Log

Coordinates (Lat, Lon WGS84)

47.53808, -122.03733 (est)

Exploration Number

ASB-02

Contractor

Cascade

Equipment

CME 75 truck rig

Sampling Method

Autohammer; 140 lb hammer; 30" drop

Ground Surface (GS) Elev. (NAVD88)

77' (est)

Operator

James

Exploration Method(s)

Hollow stem auger

Work Start/Completion Dates


10/18/2019

Top of Casing Elev. (NAVD88)

NA

Depth to Water (Below GS)

12.5' (ATD)



Legend

□ No Soil Sample Recovery

■ Split Barrel 2" X 1.375" (SPT)

Plastic Limit — Liquid Limit

▽ Water Level ATD

Water Level

See Exploration Log Key for explanation of symbols

Logged by: IVT
Approved by: RPK

Exploration Log
ASB-02

Sheet 1 of 2

**Brown Bear - Issaquah - 080109**

Project Address & Site Specific Location
55 NW Gilman Blvd Issaquah, WA 98027, W of Chevron Station, NW of ASB-01

Geotechnical Exploration Log

Coordinates (Lat, Lon WGS84)
47.53808, -122.03733 (est)

Exploration Number

ASB-02

Contractor

Cascade

Equipment

CME 75 truck rig

Sampling Method

Autohammer; 140 lb hammer; 30" drop

Ground Surface (GS) Elev. (NAVD88)

77' (est)

Operator

James

Exploration Method(s)

Hollow stem auger

Work Start/Completion Dates

10/18/2019

Top of Casing Elev. (NAVD88)

NA

Depth to Water (Below GS)

12.5' (ATD)

Depth (feet)	Elev. (feet)	Exploration Completion and Notes	Sample Type/ID	Blows/foot	Water Content (%)	Blows/6'	Tests	Material Type	Description	Depth (ft)
				0 10 20 30 40 50						
						50/6"	ASB-02-20.0 Sheen = Slight Odor = None PID = <1 ppm		SAND WITH SILT (SP-SM); very dense, wet, brown-gray; fine to coarse sand SILTY GRAVEL WITH SAND (GM); very dense, wet, brown-gray; fine to coarse sand, fine to coarse gravel	
55						5/6"	ASB-02-22.5 Sheen = Slight Odor = None PID = <1 ppm		silt (ML) interbed (2" thick)	
25						10 25 30	ASB-02-25.0 Sheen = None Odor = None PID = 1.4		SILTY SAND (SM); very dense, wet, brown-gray; slow dilatancy; fine to coarse sand fine to coarse gravel layer (3" thick)	25
50						11 27 42	Sheen = None Odor = None PID = 2.7		SILTY SAND WITH GRAVEL (SM); very dense, very moist, brown-gray to light brown; fine to coarse sand; fine gravel	
30						32 50/6"	Sheen = None Odor = None PID = 1.2		increased silt content	30
45									Bottom of exploration at 31 ft. bgs. Note: Boring elevations not surveyed for this project.	
35										35
40										

Legend
☐ No Soil Sample Recovery

☒ Split Barrel 2" X 1.375" (SPT)

Plastic Limit — Liquid Limit

Water Level ATD

Water Level

See Exploration Log Key for explanation of symbols

 Logged by: IVT
Approved by: RPK

Exploration Log
ASB-02

Sheet 2 of 2

APPENDIX B

Report Limitations and Guidelines for Use

REPORT LIMITATIONS AND GUIDELINES FOR USE

This Report and Project-Specific Factors

Aspect Consulting, LLC (Aspect) considered a number of unique, project-specific factors when establishing the Scope of Work for this project and report. You should not rely on this report if it was:

- Not prepared for you
- Not prepared for the specific purpose identified in the Agreement
- Not prepared for the specific real property assessed
- Completed before important changes occurred concerning the subject property, project or governmental regulatory actions

Geoscience Interpretations

The geoscience practices (geotechnical engineering, geology, and environmental science) require interpretation of spatial information that can make them less exact than other engineering and natural science disciplines. It is important to recognize this limitation in evaluating the content of the report. If you are unclear how these "Report Limitations and Use Guidelines" apply to your project or site, you should contact Aspect.

Reliance Conditions for Third Parties

This report was prepared for the exclusive use of the Client. No other party may rely on the product of our services unless we agree in advance to such reliance in writing. This is to provide our firm with reasonable protection against liability claims by third parties with whom there would otherwise be no contractual limitations. Within the limitations of scope, schedule, and budget, our services have been executed in accordance with our Agreement with the Client and recognized geoscience practices in the same locality and involving similar conditions at the time this report was prepared

Property Conditions Change Over Time

This report is based on conditions that existed at the time the study was performed. The findings and conclusions of this report may be affected by the passage of time, by events such as a change in property use or occupancy, or by natural events, such as floods, earthquakes, slope instability, or groundwater fluctuations. If any of the described events may have occurred following the issuance of the report, you should contact Aspect so that we may evaluate whether changed conditions affect the continued reliability or applicability of our conclusions and recommendations.

Discipline-Specific Reports Are Not Interchangeable

The equipment, techniques, and personnel used to perform a geotechnical or geologic study differ significantly from those used to perform an environmental study and vice versa. For that reason, a geotechnical engineering or geologic report does not usually address any environmental findings, conclusions, or recommendations (e.g., about the likelihood of encountering underground storage tanks or regulated contaminants). Similarly, environmental reports are not used to address geotechnical or geologic concerns regarding the subject property.

We appreciate the opportunity to perform these services. If you have any questions please contact the Aspect Project Manager for this project.

Tab 8.0

8.0 OTHER PERMITS

- City of Issaquah Building Permit
- City of Issaquah Grading Permit
- City of Issaquah Right-of-way Permit
- City of Issaquah Fire Permit
- City of Issaquah Sign Permit

Tab 9.0

9.0 OPERATIONS AND MAINTENANCE MANUAL

An Operations and Maintenance Manual will be provided in this section during Final Engineering Review.

Tab 10.0

10.0 DECLARATION OF COVENANT FOR PRIVATELY MAINTAINED FLOW CONTROL AND TREATMENT FACILITIES

A Declaration of Covenant for Maintenance and Inspection of Onsite Stormwater BMPs will be provided in this section during final engineering review.

Tab 11.0

11.0 DECLARATION OF COVENANT FOR PRIVATELY MAINTAINED ON-SITE STORMWATER MANAGEMENT BMPS

A Declaration of Covenant for Maintenance and Inspection of Onsite Stormwater BMPs will be provided in this section during final engineering review.

Tab 12.0

12.0 BOND QUANTITIES WORKSHEET

A completed Bond Quantities Worksheet will be provided in this section during Final Engineering Review.